BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-69

Name of Work:-Maintenance of BBMP office in ward no 04, Yelahanka Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAJESH A (R R ENGINEERING WORKS ..)	
				Rate	Rate In Words
1	BBMP office Cleaning materials for office use only (for 1 year maintenance)				
2	Visitor Chairs with arms	Nos	26.00	3350.00	Rupees Three Thousand Three Hundred Fifty Only
3	High back chair	Nos	3.00	6556.00	Rupees Six Thousand Five Hundred Fifty Six Only
4	Writing table. Mobile pedastal	Nos	1.00	22771.00	Rupees Twenty Two Thousand Seven Hundred Seventy One Only
5	Standard table kit	Nos	1.00	17077.50	Rupees Seventeen Thousand Seventy Seven and Paise Fifty Only
6	KSRB 13-8.11 Providing and fixing to wall, ceiling and floor, low-density polyethylene pipes 10.00KGf/sq.cm. working pressure 25mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling an floor including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No. 13.2.15.1 / 13.9,, Page No. 103/ Item No. 13.76 / PWD SR 2018-19	Mtrs	20.00	105.95	Rupees One Hundred Five and Paise Ninety Five Only
7	KSRB 13-6 5.1: Providing and fixing in position 15mm nominal bore brass ferrule with C.I. mouth cover including boring and tapping the main, cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specifications NO KBS 13.3.3 / 13.14 Page No. 89// Item No. 13.43 / PWD SR 2018-19	Each	4.00	176.90	Rupees One Hundred Seventy Six and Paise Ninety Only
8	KSRB 11-3: Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580m with footrests, 100 mm S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.Specification No. KBS 11 Page No. 77/ Item No. 12.3 PWD SR 2018-19	Each	3.00	1243.19	Rupees One Thousand Two Hundred Forty Three and Paise Nineteen Only
9	Supplying and fixing/replacing of 6/16/32 Amps electrical accessories on existing switch board. Group A				Rupees Zero

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAJESH A (R R ENGINEERING WORKS ..)	
				Rate	Rate in Words
10	h) 6 Amps Bell Buzzer	Each	20.00	99.00	Rupees Ninety Nine Only
11	a) 6Amps SP Switch	Each	20.00	27.90	Rupees Twenty Seven and Paise Ninety Only
12	c) 6Amps 3Way 5 Pin Socket	Each	20.00	36.90	Rupees Thirty Six and Paise Ninety Only
13	j) 16 Amps 3 way 5 pin socket	Each	20.00	70.00	Rupees Seventy Only
14	k) 16 Amps 3 pin Top	Each	20.00	64.80	Rupees Sixty Four and Paise Eighty Only
15	l) 32 Amps Bakelite DP	Each	20.00	115.00	Rupees One Hundred Fifteen Only
16	Supply and fixing of 230 volts 20/40 watts starter for fluorescent lamp. a) Group A	Each	40.00	16.20	Rupees Sixteen and Paise Twenty Only
17	Supplying and fixing/replacing of flouresexcnt tube. a) 18 to 40 watts	Each	40.00	58.50	Rupees Fifty Eight and Paise Fifty Only
18	Supplying of 65/80 watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes.	Each	40.00	420.00	Rupees Four Hundred Twenty Only
19	Supply of Specital type lamps h) 36 Watts CFL	Each	40.00	171.00	Rupees One Hundred Seventy One Only
20	Rewinding a...mm ceiling fan/after using necessary gauge annealed and insulated copper wire with necessary insulating, separators vibration arresting shellac, etc including replacement of bearings if any transportation to and from the spot to workshop inclusive of releasing the refixing. c) 1200MM	Each	25.00	567.00	Rupees Five Hundred Sixty Seven Only
21	Releasing the existing fan dismantling testing painting after removing the existing painting by scraping and cleaning (Spray method) to less than 2 coats of approved make enamel paint to a ceiling fan and wiring and fixing of the same.	Each	25.00	220.50	Rupees Two Hundred Twenty and Paise Fifty Only
22	Releasing the existing FTL Fitting all capacities, checking, testing and installing at same place.	Each	30.00	27.00	Rupees Twenty Seven Only
23	Supplying and fixing Cordless calling bell suitable to operate on 230V 50 Hz AC/3V DC Supply, Cordless remote bell push with 2x1.5V DC Batteris and completely wired. a) Group A	Each	4.00	585.00	Rupees Five Hundred Eighty Five Only

RajeshA
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.